
Insulated Roof & Wall Panels
Australia




# JI Vulcasteel Roof Panel Installation Guide





Multiple Panels Eaves to Ridge - 150mm End Lap

#### Components



This installation guide should be read in conjunction with the 'project specific' design drawings and method statements.


Although this installation guide is deemed to be correct at the time of publication, Kingspan reserve the right to amend the information at any time in the future. Installation Guides are available for the full range of Kingspan Insulated Roof, Wall and Facade Systems.

#### Multiple Panels Eaves to Ridge - 150mm End Lap


#### Note:

- Ensure steel work is suitable for panels and is within tolerance.
- The end lap purlin position is critical, check location and straightness.
- Number of fasteners must be calculated based on project spans and wind loads.
- Ensure panels are perpendicular to gutter.
- For Under Eaves Gasket option, refer to typical JI vulcasteel Roof Panel drawing details.
- Ensure lower panel is bearing on to purlin by a minimum of 50mm.
- All sealants to suit project specification requirements.
- Protective film to be removed from external weather face of panel & internal liner, where applicable, prior to installation.
- Protective film must be removed within 3 weeks of delivery.
- Please contact Kingspan Technical Services Department for guidance
- Internal air seals
- High humidity & hygiene internal environments
- Project specific advise
- Acoustic performance
- Colour of sealants within this installation guide are for illustration purposes.
- Penetrations larger than 300mm x 300mm must be framed out with structural steel.

 Panels must be installed on an angle to allow for correct engagement of the internal liner tongue and groove.



- Ensure panel joints are pulled tight to adjacent panels to close any gaps as works progress.
- This installation guide provides generic guidance on installation methods, however, should be read in conjunction with project specific specifications and construction details.
- Install fasteners with recommended screw gun speed selection for type of steel, use correct socket and drive bit, including depth - locating nose piece, unless fastener has feature to prevent overdriving, in line with fastener manufacturers.



Multiple Panels Eaves to Ridge - 150mm End Lap

#### Fastener Layouts

crown, 35mm upslope from panel end

#### End / Side Lap


Side lap stitching screws (6.3mm Ø x 25mm long) with min. 8mm dia washers at 450mm centres (maximum)

End lap stitching screws (6.3mm Ø x 25mm long) with min. 8mm dia washers 2 per valley and 1 per


#### Ridge

Primary fasteners with minimum 19mm Ø washer, 1 at each valley at each support


#### Standard Intermediate, Eaves, End Lap & Side Lap





#### Verge





Note: Minimum number of fasteners as illustrated. Number of fasteners must be calculated on the project specific spans and wind loads. Storm washers to be used at each primary crown fixing location.



















### Panel Handling

Appropriate personnel protective equipment should always be worn to avoid cuts and abrasions to installers and panels.


Individual panels should always be lifted from a pack and not dragged over others.

The weight of individual panels for lifting can be determined from the information on the packing slip.


For larger panels the contractor would normally arrange to use appropriate material installation equipment to help lift the panels into position.

#### Protecting Film


When panels are supplied with a plastic protective film this should be removed during site installation.



The recommended loading / unloading method for bundles less than or equal to 6m is to use a single forklift with widely spaced forks placed under the centre of the bundle as shown.



The recommended lifting method for bundles no more than or equal to 6m can be handled with a crane by using nylon straps and wood spreaders as shown.




The recommended lifting method for bundles more than 6m, by crane, is by using three points of support. To prevent damage from nylon straps, use wood spreaders at top and bottom at lifting locations as shown.

### Panel Handling

Correct and Incorrect Panel Handling

#### Caution

Individual panels should never be moved in a flat position as excessive flexing may result. Excessive flexing ruptures a panel's core, permanently distorts the facings and may lead to thermal blistering. When moving a panel, it must be turned on its edge first, then supported at each end with as many men as necessary to safely handle.



lotes	

Installation guides are available for most of Kingspan insulated roof and wall panels.

For the most up to date version of this Installation guide please <u>click here</u> or scan the QR code below. Alternatively, please call Kingspan on:

AUS: +61 2 8889 3000

www.kingspanpanels.com.au



For the product offering in other markets please contact your local sales representative or visit www.kingspanpanels.com

Care has been taken to ensure that the contents of this publication are accurate, but Kingspan Insulated Panels and its subsidiary companies do not accept responsibility for errors or for information that is found to be misleading. Suggestions for, or description of, the end use or application of products or methods of working are for information only and Kingspan Insulated Panels and its subsidiaries accept no liability in respect thereof.

First Issue: 22/07/2024

