
Insulated Roof & Wall Panels
Australia

K-Clad Wall Panel Installation Guide






Kingspan Insulated Roof, Wall and Facade Systems.

Vertically Laid

Components

K-Clad Wall Panel



Vertically Laid

Notes

- Ensure steelwork is suitably lined, levelled and within tolerance.
- Panels must be installed in a tiered sequence only.
- The end lap support position is critical, check location and straightness.
- Cover plates required where gap in s support steel is greater than 20mm.
- All fasteners to be carbon steel to maintain panel warranty
- Cut side of panel to suit required width at ground level before installation of corner panels P7 and P8 to suit.
- Gun-grade sealant type neutral cure gun-grade sealant.
- The end lap support position is critical, check location and straightness.
- Number of fasteners must be calculated based on project spans and wind loads.
- See specific details for high humidity applications.
- Contact Kingspan Technical Services for project specific advice.
- Please contact Kingspan Technical Services Department for guidance
- Internal air seals
- High humidity & hygiene internal environments
- Project specific advise
- Clean swarf off panels immediately when created.
- Ensure panel joints are pulled tight to adjacent panels to close any gaps as works progress.
- This installation guide provides generic guidance on installation methods, however, should be read in conjunction with project specific specifications and construction details.
- Install fasteners with recommended screw gun speed selection for type of steel, use correct socket and drive bit, including depth - locating nose piece, unless fastener has feature to prevent overdriving, in line with fastener manufacturers.



K-Clad Wall Panel Vertically Laid

SIDELAP A Factory Applied Weather Seal (FAWS) is applied to the panels, on the under side of the sidelap, before they

leave the factory.
Sidelap rotated 180°



Continuous ledger angle

Continuous runs of 6x4mm butyl or neutral cure gun-grade butyl sealant

Continuous run of silicone sealant

Continuous base support angle

Continuous base drip flashing

Note: The ledger angle prevents the panel from sitting on the drip flashing

1


Apply continuous runs of 6x4mm butyl sealant or runs of neutral cure gun-grade butyl sealant to provide internal perimeter air seals


2


Line, level and fix drip flashing to structure. Joints in the drip flashing to incorporate butt straps sealed with two runs of neutral cure gun-grade butyl sealant


3


Fit ledger angle through drip flashing, into continuous base support angle, using low profile fasteners. An air seal consisting of continuous run of 6x4mm butyl sealant or bead of neutral cure gun-grade butyl sealant is required between drip flashing and ledger angle, and between ledger angle and K-Clad Wall Panel














Panel Handling

Appropriate personnel protective equipment should always be worn to avoid cuts and abrasions to installers and panels.


Individual panels should always be lifted from a pack and not dragged over others.

The weight of individual panels for lifting can be determined from the information on the packing slip.


For larger panels the contractor would normally arrange to use appropriate material installation equipment to help lift the panels into position.

Protecting Film


When panels are supplied with a plastic protective film this should be removed during site installation.



The recommended loading / unloading method for bundles less than or equal to 6m is to use a single forklift with widely spaced forks placed under the centre of the bundle as shown.



The recommended lifting method for bundles no more than or equal to 6m can be handled with a crane by using nylon straps and wood spreaders as shown.




The recommended lifting method for bundles more than 6m, by crane, is by using three points of support. To prevent damage from nylon straps, use wood spreaders at top and bottom at lifting locations as shown.

Panel Handling

Correct and Incorrect Panel Handling

Caution

Individual panels should never be moved in a flat position as excessive flexing may result. Excessive flexing ruptures a panel's core, permanently distorts the facings and may lead to thermal blistering. When moving a panel, it must be turned on its edge first, then supported at each end with as many men as necessary to safely handle.



lotes	

Installation guides are available for most of Kingspan insulated roof and wall panels.

For the most up to date version of this Installation guide please <u>click here</u> or scan the QR code below.

Alternatively, please call Kingspan on:

www.kingspanpanels.com.au

AUS: +61 2 8889 3000



For the product offering in other markets please contact your local sales representative or visit www.kingspanpanels.com

Care has been taken to ensure that the contents of this publication are accurate, but Kingspan Insulated Panels and its subsidiary companies do not accept responsibility for errors or for information that is found to be misleading. Suggestions for, or description of, the end use or application of products or methods of working are for information only and Kingspan Insulated Panels and its subsidiaries accept no liability in respect thereof.

