
Kingspan
Membrane
Lined
Insulated
Gutter
Installation
Guide







Components



This installation guide should be read in conjunction with the 'project specific' design drawings and method statements.

Although this installation guide is deemed to be correct at the time of publication, Kingspan reserve the right to amend the information at any time in the future. Installation Guides are available for the full range of Kingspan Insulated Roof, Wall and Facade Systems.

Note:

- Only operatives who have taken part in the Kingspan product training should carry out heat welding operations
- Ensure steel work is suitable for Gutter and is within tolerance.
- To prevent foot traffic contamination, membrane gutter joints to be fully welded across full girth of gutter as works progress, prior to panel installation.
- Membrane cover strip to be installed gloss face down.
- Gutter Joints should be kept clean and dry prior to welding.
- Should dirt and moisture contaminate a joint prior to welding, it should be cleaned with a mild detergent solution and thoroughly dried with a linen cloth.
- Should a joint be contaminated with oil or grease prior to welding it should be cleaned with either alcohol or acetone and thoroughly dried.
- Any drilling swarf and redundant fixings must be removed from gutter surface as works progress to prevent damage to the membrane
- Use panel clamps to ensure full engagement of panel joint when required.
- Protective film to be removed from external weather face of panel & internal liner where applicable prior to installation.
- Clean swarf off panels immediately when created.




Note: Ensure steel work is suitably lined, levelled and within tolerance. Each gutter length must be fully installed prior to access


Note: Any drilling swarf and redundant fixings must be removed from gutter surface as works progress to prevent damage to the membrane


Locate stop end/mitred corner/tee junction and 50mm lap on internal liner work away from section, denotes direction of lay ensuring the gutter is Note: Left hand example shown correctly aligned and Starter direction of lay is followed. Direction of lay Fasten gutter at 1500mm centres with min. 2 No. multigrip carbon steel rivets (grip range 1.5mm -9mm) per gutter wing

Note: Gutter joints should be kept clean and dry prior to welding. Should dirt and moisture contaminate a joint prior to welding, it should be cleaned with a mild detergent solution and thoroughly dried with a linen cloth. Should a joint be contaminated with oil or grease prior to welding it should be cleaned with either alcohol or acetone (ensure compliance with any safety recommendations) and thoroughly dried



Note: To prevent foot traffic contamination, membrane gutter joints to be fully welded across full girth of gutter as works progress, prior to panel installation 50mm of membrane hot air welded at edaes 10 Membrane cover strip roll is provided 250mm x 1.5mm. Material to be cut Lay membrane cover strip to length using scissors centrally over gutter joint, and Note: Membrane cover strip to be hot air tack weld to hold in installed gloss face down position. Pre weld the cover strip, approx. 50mm from the edge and then fully weld the strip 50mm along Apply 100mm wide both edges whilst applying roller silver foil tape (silicone) pressure to ensure weld centrally over joint good weld - indicated by visible Note: Hot air welding should be carried fusion line Starter out by an experienced membrane welding contractor using electric heat gun at approx. 380 - 420°C, subject to ambient temperature Intermediate Direction of lay When cooled, test the finished weld with a seam probe and re-weld where necessary






Insulated Gutter Handling

Appropriate personnel protective equipment should always be worn to avoid cuts and abrasions.

Individual Gutters should always be lifted from a pack and not dragged over others.

The weight of individual Gutters for lifting can be determined from the information on the packing slip.

For larger panels the contractor would normally arrange to use appropriate material installation equipment to help lift the panels into position.



The recommended loading / unloading method for bundles less than or equal to 6m is to use a single forklift with widely spaced forks placed under the centre of the bundle as shown.

Notes		

Installation guides are available for most of Kingspan insulated roof and wall panels. For the most up to date version of this Installation guide please click here or scan the QR code below. Alternatively, please call Kingspan on:

AUS: +61 2 8889 3000 www.kingspanpanels.com.au



For the product offering in other markets please contact your local sales representative or visit www.kingspanpanels.com

Care has been taken to ensure that the contents of this publication are accurate, but Kingspan Insulated Panels and its subsidiary companies do not accept responsibility for errors or for information that is found to be misleading. Suggestions for, or description of, the end use or application of products or methods of working are for information only and Kingspan Insulated Panels and its subsidiaries accept no liability in respect thereof.

Please scan for the most up to date version of this Installation Guide.

